ST. LUKE'S CHURCH ISLE OF WIGHT COUNTY, VA. NEAR SMITHFIELD HABS NO. 11-20 HABS VA. 47-SMIFY

PHOTOGRAPHS
WRITTEN HISTORICAL AND DESCRIPTIVE DATA
DISTRICT NO. 11

HISTORIC AMERICAN BUILDINGS SURVEY
PHILIP N. STERN, DISTRICT OFFICER
21 LAW BLDG., FREDERICKSBURG, VA

HABS VA HT-SMIF.V

1 .--

ST. LUKE'S CHURCH Near Smithfield Isle of Wight County Virginia

Owner: Episcopal Church.

Date of Erection: Between 1632 and 1682.

Architect: No record.

Builder: No record.

Present Condition: Good.

Number of Stories: One; tower, three.

Materials of Construction: Brick.

Other Existing Records: Virginia Carolorum, by Neill, E.D., page 263, says St. Luke's Church was built some years after 1638; page 263, the first brick church in Virginia (at Jamestown) was commenced in 1639.

Additional Data: See the following pages:

Virginia Colonial Churches (1908), 80.

Brock, H.I., Colonial Churches in Virginia.

Lancaster, R.A., Jr., Historic Virginia Homes and Churches, 49.

Kimball, F., American Architecture: opp. page 28.

Tallmadge, T.E., The Story of Architecture in America, 30.

Embury, Aymar, II, Early American Churches, 20.

Ware, W.R., The Georgian Period, 21, 59.

Coffin and Holden, Brick Architecture of the Colonial Period

in Maryland and Virginia, 21.

Briggs, Hemes of the Pilgrim Fathers in England and America.

Hamlin, T.F., The American Spirit in Architecture, 48.

Jackson, J., American Colonial Architecture, 28.

Photograph in architectural collection of Fine Arts Division.

ST. LUKE'S CHURCH Isle of Wight County, Va. Near Smithfield

## HISTORICAL DATA

St. Luke's, or as it was called prior to the Revolution: "The Old Brick Church", was built under the care of Joseph Bridger, sometime between 1632 and 1682, in what was then Warrescoyack Parish, later divided in 1642 into Newport and Warrescoyack.

The church is remarkable as the only remaining example of a buttressed Gothic Church of the early seventeenth century in America.

about the first quarter of the lath century when it fell into disrepair. In 1887 the roof fell in carrying down part of the walls. The building remained in a state of disuse until a restoration was begun in 1890 under the direction of the Rev. David Barr, then rector of the Church. The work was completed about 1897. The present stained glass was set in at this time.

Reference: Finlay F. Ferguson, Jr.

Hillip h. Stern

Reviewed 1936, 74. C. F.